

Miller Center

Fly System: Miller Center is a non-conventional Fly System; there are 11 Thern Winches hand crank winches. One rotation of the drum is 3/4's of an inch and takes about 5 minutes to crank a pipe from the floor to a trim of 24 feet.

Line Schedule: All Measurements from Plaster Line

Description	From P L	Trim Height	General Information
Main Curtain Dead Hung	1'-4"	23'-0"	
#1 Border Winch #1	2'-7"	Pipe 24'-8"	18'-8" Bottom of Border
Traveler Legs for Movie Dead Hung	2'-11"	21'- 0" To Pipe	
#1 Electric Winch #2	4'-0"	22'-0" To Pipe	
Movie Screen Winch #3	5'- 9"		Movie Screen cannot move
#2 Border Winch #4	7'- 6"	24' - 4" To Pipe	18' - 4" Bottom of Border
#2 Legs Dead Hung	7' - 11"	22'- 1" To Pipe	
#2 Electric Winch #5	8' - 9"	21'-10"	
Empty Pipe Winch #6	11'- 6"		
#3 Border and Legs Dead Hung	12'-7"	24'-0" To Pipe	18' - 0" Bottom of Border
#3 Electric Winch #7	14'- 1"	21'-3"	
Empty Pipe Winch #8	16' - 9"		
#4 Border and Legs Dead Hung	17' - 10"	24' - 0" To Pipe	18'-0" Bottom of Border
#4 Electric Winch #9	19'- 3"	21'-1"	
Cyc Light Pipe Dead Hung	20' - 11"	22' - 2"	5 - Aurora 3 cell Cyc units
Empty Pipe Winch # 10	21'- 10"		
Traveler	24' - 3"	22'-7"	Pulley Stage Right
Cyc Winch #11	25'-10"		

Thern Winches are numbered

House Main Curtain is a Traveler with a center split, Control is from Stage Left.

All Batons are 55 feet long.

1st Electric has 24 circuits, numbers 35 thru 58

2nd Electric has 14 circuits, numbers 59 thru 72

3rd Electric has 14 circuits, numbers 73 thru 86

4th Electric has 16 circuits numbers 87 thru 102

All circuits numbers run from Stage Right to Stage Left. Yes you read correctly. The numbering was done backwards.

Height from the floor to the I Beam is 36 feet.